

RAJASTHAN UNIVERSITY LIBRARY DATE LABEL Call No. D. 26, B. 2825 IV No. 4 Date of Release Accn. No. 18152 for loan This book should be returned to the library on or before the date last stamped below.



PROTECTIVE IRRIGATION WOR RAJPUTANA.

REPORT

ON THE

BHULA PROJECT, NEAR ROHERA,

IN THE

SIROHI STATE.

AJMER

PRINTED AT THE RAJPUTANA MISSION PRESS.

INDEX.

Para	Λ.					PAGE.
1.	Source and course of the	Nullah	• •••	••	•••	5
2.	Work started in the Fam	ine of 1	900	•••	•••	5
3.	Water available for stora	ge	•••	•••	•••	5
4.	Cost of original Project	•••	•••	•••	••	5
5.	Disadvantages of Site	•••	•••	•••	•••	5
6.	Site inspected by Consult	ting Eng	ineer for	Irrigatio	n and	:
	directions given by hir	n	•••	•••	•••	·5 .
7.	Land available for Irriga	tion	•••	•••	•••	6
8.	Storage capacity at differ	ent Con	tours	•••	•••	6
9.	Capacity of Storage Reso	ervoir	•••	•••	•••	G
10.	Weir	••	•••	•••		7
11.	Dam	•••	• • •	•••	•••	7
-13.	Outlet Sluices	•••	•••	•••	•••	7
14	Canal No. 1	••	•••	•••	•••	8
15.	Sluice No. 2	•••	••	•••	•••	8
16.	Canal No. 2	•••	•••	•••	•••	9
17.	Materials	•••	•••		•••	9
18.	General Abstract of cost	•••	•••	•••	•••	9
19.	Value of water stored	•••	•••		•••	9
20.	Probable Revenue	•••	•••	• • •	•••	. ,9
21.	Preparation of Project	•••	•••	•••	•••	\$}
22-29.	Specification	•••	•••	😯	• •••	$\cdot \mathfrak{g}$
	Abstract Estimate of Co	st	•••	•••	• •••	11 🔬

PLANS.

I - Index Plan.

II.-General Contour Plan.

111.—Plan and Longitudinal Section of Dam

IV.—Cross Section of Dam.
V.—Weir and Sluice.

SIROHI STATE.

BHULA PROJECT, NEAR ROHERA.

1. Seven nullahs which rise and have a drainage area of 35 square miles in the Aravellis, unite and pass through a low range of hills near Bhula, which is about 3 miles south-east of the village of Rohera. The nullah so formed joins the left bank of the large Waloria Nullah at Rohera, then passes on in a south-west direction for 9 miles, till it flows into the left bank of the Western Banas at Kivarli.

Source and Course of the Nullah

2. During the Famine of 1900 work was begun on the construction of a Dam across the gap in the hills near Bhula, but all that exists is a deep trench which was dug for the foundations of the core-wall, and some 59,000 c.ft. of broken stone ballast stacked at the site, for concrete; and some concrete consolidated at the north end.

Work started in the Famine of 1900.

The value of this ballast at Rs. 3 per 100 c.ft. has been credited in the Estimate, as it can be used in the concrete foundations whenever the work is taken in hand.

3. From the 35 square miles of hilly catchment it would be safe to anticipate that 20 per cent. of the average rainfall of 23½ inches is available for storage, or 383 m.c.ft.

Water available for storage

4. As the Famine work had been carried out without any Plans and Estimate, Surveys were taken to see what it would cost to complete the work, and it was found that with weir level at 40 ft. above bed of nullah, giving a capacity of 320 m.c.ft., the approximate cost for Dam, Weir, and Sluices would be Rs. 1,45,000.

Cost of original Project.

The Dam would have been about 1,400 r.ft. in length, including a length of 310 r.ft. at the north end, where it was proposed to make a masonry Dam to serve as a waste weir, partly cut into the hill side.

5. The disadvantages of the site are :-

Disadvantages of Site

- (a) The unsatisfactory nature of the soil at the site of the bund, necessitating a deep masonry core-wall, and great expense.
- (b) The difficulty of getting a good escape.
- (c) The large area of land below already irrigated by wells.
- 6. The Consulting Engineer for Irrigation inspected the site in November 1903, and pointed out these defects to the Project, and directed Surveys to be taken to ascertain—
 - (a) The area and value of the land which will be submerged.

Site inspected by Consulting Engineer for Irrigation, and directions given by him.

- (b) The area of the land commanded; how much of this is already cultivated; and how much is watered by wells.
- (c) And with the information so obtained to complete the Project, in case the work should be carried out later, and some use made of the expenditure incurred.

Land available for Irrigation. 7. This Survey has now been done, and it is found that-

· (a)	Wells.	Area already Irrigated by wells.	Area available for Irrigation.
On left bank of nullah On right bank of ,,	38 42	Acres. 359 299	Acres. 778 443
Total	80	658	1,221

(b) With Weir level R.L. 140 (Weir level originally proposed), 7 wells and 32 acres of land irrigated by wells will be submerged; but that with weir level at 130 only 3 wells and 13 acres of well land are submerged.

To irrigate the land available, the storage reservoir should therefore be constructed with a capacity of not less than 122 m.c.ft., allowing 100,000 c.ft. of water per acre.

Storage capacity at different contours.

ì

8. The following table shows the waterspread area, and contents of the storage reservoir at different contours. R. L. 100 has been taken to be bed level of the nullah at site of Dam:—

R.L.	Watorspread s.ft.	Capacity in m.c.ft.
150	38,200,000	} }323 <u>:</u> 00
140	26,400,000	J) '
130	14,720,000	}205·60 }100·80
120	5,440,000	35.20
110 .	1,600,000	h l
Bed level	••••	5 33
	Total	669-93

Capacity of Storage Reservoir.

9. We shall, therefore, be on the safe side if we take R.L. 130 as Weir level, giving a capacity of 136 m.c.ft. available for irrigation. Rs. 2,150 has been provided in the Estimate as compensation for the 3 wells and 13 acres of well land which will be submerged.

10. The Weir will still have to be on the hill at the north end of the Dam where there is rock, as levels* show that there is no saddle in the range of hills, away from the Dam, low enough to cut away for the escape; but at the lower Weir levelnow proposed the objection to this position is reduced, though a water cushion will still be necessary, and has been provided.

The maximum discharge, by Dicken's Formula, on the catchment area of 35 square miles is 11,863 ft. per second, and with a 7 ft. discharge a Weir 185 ft. in length is required.

Flood level will be R.L. 137; and the top of Dam R.L. 141.

11. The Dam (see Plan No. 3) starts from the south end of the Weir, and is 1,063 ft. in length, closing the gap in the range of hills through which the nullah flows.

It will be of earth, with a core-wall of masonry in lime 11 ft. in thickness at top, increasing 6 inches at every 5 ft. depth by 3" offsets on either

As no rock for foundations is available, the core-wall will be taken down 15 ft. below bed level, or half the depth of water against the Dam.

The earthwork in front of the core-wall starts at flood level with a terrace 5 ft. in width at top, and has a 3 to 1 slope.

This front slope and the 5 ft. terrace will be protected with a 1 ft. layer of stone-pitching on 6 inches of kunker.

The earthwork in rear starts 2 ft. below the top of the core-wall, is 10 ft. in width at top, and has a 2 to 1 slope (see Plan No. 4).

Two outlet Sluices are provided.

Sluice No. 1 is at the south end of the Dam, and Canal No. 1 leads from it to irrigate the 778 acres available on the left bank.

The design consists of two chambers, with a 11 ft. diameter Sluice fixed in the main wall dividing them, capable of discharging 10.8 c.ft. per second with I ft. head; and at this rate the 78 m.c.ft. of water required for the 780 acres available would be discharged in three months.

But the Sluice must also be large enough to supply all the water required for the first watering for the area available within about 30 days, as the demand is simultaneous, and it is of no use offering water when the time is past.

If we allow 1 c.ft. of water on the area as required for one watering, to be delivered in 30 days of 12 working hours, we get $\frac{\text{Acres } \text{ } \text{ } \text{f.t. per acre.}}{30 \times 12 \times 60 \times 60} = 26 \text{ c.ft.}$ per second as the discharge required.

With the mean head of 10 ft. and the total area could not be irrigated with less water stored—the 11 ft. diameter sluice will discharge 34.39 c ft. per second, so satisfies the requirements.

^{*} Note.—The level of lowest Saddle is R.L. 167 or 37 ft above Wein

13. The face wall of the outer chamber is provided with double grooves 1½ ft. apart for Sluice boards, into which planks can be put with earth rammed between to shut off the water at any time, so that the Sluice may be examined and repaired if necessary. An iron grating with vertical bars is also provided to prevent brushwood, or anything likely to block the pipe or valve, passing into the Sluice well.

Wing walls with steps have also been provided in continuation of the Sluice well.

Ladders, consisting of 1 inch round iron bars are to be fixed to the sides of each well to enable descent to the Sluice valves.

The Sluice will be of cast-iron with gun-metal faces, fitted with two valves, one outside the Sluice well, and the other inside, so that if one valve gets out of order the other can be closed at once and opened after the necessary repairs have been carried out. The valves to be opened by vertical rods with screwed heads.

The screw wheel at the top to show clearly how much the valve is open at any time.

A wooden platform on iron rails is provided from which to work the Sluices.

A masonry arched Sluice drain passes from the Sluice well under the Dam connected with Canal No. 1.

Canal No 1

14. Canal No. 1 has been surveyed for $3\frac{1}{2}$ miles (see Plan No. II) for the first 2 miles, where it has a fall of 2 ft. per mile, the section required to discharge 26 c.ft. per second is 3 ft. bed width, and 3 ft. depth, with side slopes 1 to 1;

For the 3rd mile the fall is 3 ft. per mile and for this length the section will be 3 ft. bed width with $1\frac{3}{4}$ ft. depth; and for the last $\frac{1}{2}$ mile where the fall is 4 ft. per mile, 3 ft. bed width and $2\frac{1}{2}$ ft. depth.

Sluice No 2

15. Sluice No. 2 is in the masonry Dam at the north end of the Weir, and consists of a circular outer well of masonry (see Plan No. V) connected with the masonry Dam, and provided with an opening, up the face, 3 ft. in width, provided with an iron grating and grooves for boards, as in the face wall of Sluice No. 1.

The inner chamber is a circular well 6 ft. diameter, built in the masonry Dam, the Sluice, which is 1 ft. in diameter, being fixed in the wall dividing the 2 chambers, a sluice valve being in each; the water is discharged through a 1 foot diameter cast iron pipe built in the masonry Dam, connected with Canal No. 2.

The Sluice can discharge 5½ c.ft. per second with 1 ft. head, or the 45 m.c.ft. of water required for the 450 acres available in a little over 3 months.

With the mean head of 10 ft., it will discharge 15½ c.ft. per second, which is sufficient to give 1 c.ft. of water over the whole 450 acres in 30 days of 12 working hours.

16. Canal No. 2 has been surveyed with a fall of 2 ft. per mile for canal no 2 23 miles, where it tails into the Waloria Nullah.

To discharge 151 c.ft. per second, it will require a 4 ft. bed width, 2 ft. depth and side slopes of 1 to 1.

17.	(u)	Building	stone is	procurab	le at site.
-----	-----	----------	----------	----------	-------------

Materials

- (b) Slabs will be brought from Pindwara, a distance of 10 miles.
- (c) Kunker is available near Rohera, at a distance of 3 miles.
- (d) Wood for fuel is procurable at site.

	` /			•				· Rs. 1	
18.	Dam		•••	•••		•••		51,519	General Abstract
	Weir	•••	•••		••	••		21,149	of cost.
	Lower	Weir t	o form	water	cushi	on	•••	8,051	·
	Sluice	No. 1	•••	•••	••	•••	•••	5,457	
	Sluice	,, 2	•••	•••	•••	•••	•••	, 927	
	Canal	No. 1	•••		•••	***	•••	2,474.	
	Canal	,, 2	••	•••	•••	•••	•••	1,160 👾 🦠	
	Compo	enention		•	•••	***	•••	2.150	
						Total ·	•••	92,957	
	Contin	igencies	(ij 3	per cei	nt	••	•••	- 4.648 	
						Total	•	97,605	
		t value 3 Rs p				allast aț		1,770	
									•

Total

19. It is an expensive Project, and the value of water stored is 1,419 : v. c.ft. per rupec.

Value of water , stored

20 If all the land available, 1,221 acres, is brought under cultivation and irrigated, allowing Rs. 4/ per acre, an annual Revenue of Rs. 4,884 should be realized or slightly over 5, per cent, profit on the capital cost.

Probable Revenue

21. The Surveys were made and Plans prepared by Suboverseer Luxmi Narain, under the directions and supervision of the Superintending Engineer, Protective Irrigation Works, Rajputana.

Proparation of Project

SPECIFICATION.

22. All the dimensions of the Dam are given in the Plans and Estimate, which are to be strictly adhered to.

Dimen slons

23. The centre line and the side slopes to be marked out with trenches 1½ ft. broad and 1 ft. deep. Showing permanently the inner and outer slopes, and the breadth of the top of the embankment.

Marking out

24. The embankment will be carried out in layers not exceeding 9" Earthwork in thickness carefully consolidated.

No clods of earth should on any account be allowed in the embankment.

No earth to be excavated within 200 ft. of either toe of the slopes.

Canals.

25. All the cutting to be done as per section, with required slopes in bed. All the excavated earth to be stacked in spoil banks, leaving a berm of 10 ft. (width to be reduced if valuable land is crossed) on either side of the canal.

Pitching.

26. The surface of the inner slope and the terrace at top to be protected by a layer of dry rubble stone 1 ft. thick over 6" of kunker.

Masonry.

27. The masonry of the core-wall, outlet sluices weir, &c., to be of rubble set in lime mortar; only hard and durable stones to be used; and the masonry to be kept wet during construction. All the stones to be hammer-dressed, and to break joint in the same as well as in the successive courses.

All stones are to be laid on their natural beds; where there is batter the beds of the stones are to be at right angles to the batter.

Hollows between the larger stones to be filled in with smaller ones completely embedded in mortar. No empty hollow to be left nor spaces filled wholly with mortar or rubbish where pieces of stones ought to have been inserted.

The faces of the masonry in contact with the earth to be left quite rough and those remaining exposed to be smoothed and pointed with lime mortar.

Concrete

28. The concrete to consist of 3 parts broken stones to 1 part lime mortar well mixed together before putting in foundations, and to be laid in 6 inch layers and well rammed.

Lime Mortar. 29. The lime to be of good hard kunker burnt in wood fuel; cowdung to be only used for igniting the fire and never to exceed more than 1 per cent.

The mortar to consist of 1 part of lime to 1½ parts clear sand or surkee.

F. St.-G. MANNERS SMITH,

AJMER:

SUPERINTENDING ENGINEER,

13th August 1904.

Protective Irrigation Works, Rajputana.

ABSTRACT ESTIMATE OF COST. Bhula Project near Rohera, in Sirohi State.

Quantit cr No.		Items.			Rate.	Per	r.	Amount.	T	
		D	\M.			Rs.			Rs.	,
190,884	c.ft	Excavation	•••	•••		8	1,000	c. ft.	1,527	
75,363	,,	Concrete		•••		10	100	"	7,536	
133,263	,,	Masonry	•••	•••	•••	18	100	"	23,987	
3,080,897	"	Earthwork	•••	•••		5	1,000	,,	15,404	
102,159	71	Pitching	•••	•••	•••	5	1,000	"	3,065	
64,577	,,	Weir wir Excavation, i				15	1,000	27~-	969	ξ
14,940	,,	Concrete	•••		•••	10	100	,,	1,494	
109,812	1)	 Masonry	•••	•••		18	100	,,	18,686	
•	.,	Lower Wein To) FORM 1	VATER C						2
43,088	"	Excavation, i				15	1,000	,,,	646	
750	"	Concrete	•••	•••	•••	10	100	,,	750	
28,570	17	Masonry	•••	•••	•••	18	100	"	5,142	
10,692	**	Pitching	•••	•••	•••	3	100	37	321	
17,028	,,	Concrete bloc	ks	•••	•••	7	100	"	1,192	
14,590	,,	Excavation, i	or No. neludir 		cent-	15	1,000	"	219	
7,647	,,	Concrete	•••	•••	•••	10	100	"	765	
2,210	,,	Masonry Flooring	Found	ation	and	18	100	,,	398	
15,872	"	Masonry Sup	erstru	cture	•••	. 18	100	,.	2,857	
693	,,	Arch Mason	У	•••	***	24	100	; ;	166	
517	s.ft.	Stone work	•••	•••	•••	As. 8	s.ft		259	
1	No.	Sluice valve	t¼" dia:	m.	**	Rs. 350	enc	lı	350	
105	s.ft.	Iron Grating	•••	•••		,, 1	s.ft	ī.	105	
69	c.ft.	Woodwork	•••	••	•••	" 3	c.ft	• د	207	
58	r, ft.	Girders (Raile	3)	•••	•••	" 1	r.fi	t.	58	
290	"	Rod Iron 1" ladders	diamr. 	for ver	rtical	As. 4	,,		73	

6